

## 2.0 KOS KERJA-KERJA AM

### 2.1 PERATURAN KOS KERJA AM (GENERAL ITEMS) KE ATAS KOS KERJA PEMBINA - Mengikut Butiran Terperinci

BIL	KETERANGAN KERJA	UNIT	PURATA & JULAT HARGA BAGI TAHUN (%)				*PURATA & JULAT KESELURUHAN (%)	
			2008		2009		Purata	Julat
			Purata	Julat	Purata	Julat		
<b>A</b>	<b><u>Contractual Requirement</u></b>							
1	Contractor's All Risk		0.53	0.11 - 1.09	0.54	0.20 - 1.09	0.50	0.11 - 1.09
2	Insurance Of Works		0.40	0.08 - 0.90	0.34	0.14 - 0.90	0.40	0.08 - 0.90
3	Performance Bond		-	-	0.62	0.20 - 1.23	0.60	0.20 - 1.23
4	Perkeso / SOCSO		0.18	0.03 - 0.45	0.18	0.10 - 0.27	0.20	0.03 - 0.45
5	Public Liability Insurance		0.34	0.16 - 0.57	0.35	0.16 - 0.57	0.40	0.16 - 0.57
<b>B</b>	<b><u>Engineer / SO / PD's Requirement</u></b>							
1	Establishment & Removal Of SO's Site Office		0.67	0.34 - 1.29	0.68	0.56 - 0.82	0.70	0.34 - 1.29
2	Establishment, Maintenance & Removal Of SO's Site Office		0.96	0.24 - 2.95	0.36	0.24 - 0.51	0.70	0.24 - 2.95
3	Maintenance Of SO's Site Office		0.43	0.01 - 1.30	0.57	0.01 - 1.30	0.50	0.01 - 1.30
4	Laboratory Equipment		0.15	0.15	0.15	0.15	0.20	0.20
5	Pre & Post Survey		1.38	0.06 - 6.48	0.98	0.97 - 1.00	1.20	0.06 - 6.48
6	Preparation & Submission Of 'As Built Drawings'		0.33	0.00 - 1.67	0.29	0.00 - 0.57	0.30	0.00 - 1.67
7	Progress Photographs		0.06	0.01 - 0.33	0.09	0.02 - 0.33	0.10	0.01 - 0.33
8	Progress Report		0.13	0.02 - 0.33	0.16	0.08 - 0.33	0.20	0.02 - 0.33
9	Project Signboard		-	-	0.18	0.05 - 0.45	0.20	0.05 - 0.45
10	Setting Out		0.57	0.15 - 2.04	0.60	0.17 - 0.82	0.60	0.15 - 2.04
11	Surveying Equipment		-	-	1.26	0.10 - 2.92	1.30	0.10 - 2.92
12	Testing & Sampling		0.14	0.12 - 0.16	0.14	0.12 - 0.16	0.20	0.12 - 0.16
13	Work Programme		0.07	0.01 - 0.13	0.10	0.10	0.10	0.01 - 0.13

\* Purata Keseluruhan (%) (rounded up) yang ditetapkan

## 2.0 KOS KERJA-KERJA AM

### 2.1 PERATURAN KOS KERJA AM (GENERAL ITEMS) KE ATAS KOS KERJA PEMBINA - Mengikut Butiran Terperinci

BIL	KETERANGAN KERJA	UNIT	PURATA & JULAT HARGA BAGI TAHUN (%)				*PURATA & JULAT KESELURUHAN (%)	
			2008		2009		Purata	Julat
			Purata	Julat	Purata	Julat		
<b>C</b>	<b><u>Contractor's Requirement</u></b>							
1	Clearing & Cleaning Up Upon Completion		0.2	0.05 - 0.39	0.16	0.07 - 0.33	0.20	0.05 - 0.39
2	Establishment, Maintenance & Removal Of Contractor's Office		0.44	0.15 - 0.75	0.44	0.19 - 0.66	0.50	0.15 - 0.75
3	Establishment, Maintenance & Removal Of Contractor's Office, Workmen Accommodation, Store etc		0.59	0.08 - 1.63	0.75	0.16 - 1.63	0.70	0.08 - 1.63
4	Establishment, Maintenance & Removal Of Workmen's Accommodation		0.34	0.15 - 0.61	-	-	0.40	0.15 - 0.61
5	Mobilization & Demobilization Of Construction Plant & Equipment		-	-	1.16	0.32 - 4.63	1.20	0.32 - 4.63
6	Site Agent		1.01	0.23 - 1.79	1.79	1.79	1.40	0.23 - 1.79
7	Temporary Works		1.07	0.07 - 4.62	0.87	0.07 - 2.10	1.97	0.07 - 4.62

\* Purata Keseluruhan (%) (rounded up) yang ditetapkan