

3.0 KOS ITEM-ITEM KERJA

3.8 ROADS & PAVING

BIL	KETERANGAN KERJA	UNIT	PURATA KADAR HARGA KERJA BAGI TAHUN		*PURATA KADAR HARGA KERJA
			2008 (RM)	2009 (RM)	(RM)
A	<u>Kerbs</u>				
1	Construct and complete precast concrete kerbs including all necessary works	M	33.67	38.25	36.00
B	<u>Pavers</u>				
1	Insitu concrete pavers Grade 20; 25mm thick including base preparation, joints and cutting	M2	30.00	30.00	30.00
2	Interlocking concrete block; 100mm thick including all necessary works	M2	82.50	-	83.00
3	Interlocking concrete block; 80mm thick including all necessary works	M2	55.00	-	55.00
C	<u>Road Works</u>				
1	Road sub-grade preparation; in earth	M2	3.75	-	4.00
2	Road sub-base - 75mm thick granular material	M2	2.00	-	2.00
3	Road sub-base - compacted sand in 50mm thick	M2	3.50	4.00	4.00
4	Road sub-base - compacted sand in 100mm thick	M2	5.50	-	6.00
5	Road sub-base - compacted sand in 200mm thick	M2	8.00	8.00	8.00
6	Roadbase - 100mm thick crusher run	M2	8.00	40.00	24.00
7	Roadbase - 150mm thick crusher run	M2	8.38	8.38	8.00
8	Roadbase - 200mm thick crusher run	M2	11.50	11.50	12.00

* Purata Keseluruhan (rounded up) yang ditetapkan

3.0 KOS ITEM-ITEM KERJA

3.8 ROADS & PAVING

BIL	KETERANGAN KERJA	UNIT	PURATA KADAR HARGA KERJA BAGI TAHUN		*PURATA KADAR HARGA KERJA
			2008 (RM)	2009 (RM)	(RM)
9	Roadbase - 230mm thick crusher run	M2	11.50	-	12.00
10	Roadbase - 350mm thick crusher run	M2	21.00	22.00	22.00
11	Roadbase - 300mm thick laterite	M2	20.00	-	20.00
12	Roadbase - bitumen emulsion on finished surface	M2	1.47	1.10	1.00
13	Road surfacing - asphaltic concrete in 40mm thick	M2	17.75	16.50	17.00
14	Road surfacing - asphaltic concrete in 50mm thick	M2	22.55	26.10	24.00
15	Road surfacing - asphaltic concrete in 60mm thick	M2	17.88	15.50	17.00
16	Road surfacing - asphaltic concrete in 75mm thick	M2	23.50	-	24.00
17	Road surfacing - asphaltic concrete in 100mm thick	M2	42.00	43.00	43.00
18	Road surfacing - binder course in 50mm thick	M2	8.58	2.15	5.00
19	Road surfacing - binder course in 65mm thick	M2	13.00	-	13.00
20	Road surfacing - wearing course in 40mm thick	M2	12.00	-	12.00
21	Road surfacing - wearing course in 50mm thick	M2	17.00	-	17.00

* Purata Keseluruhan (rounded up) yang ditetapkan

3.0 KOS ITEM-ITEM KERJA

3.8 ROADS & PAVING

BIL	KETERANGAN KERJA	UNIT	PURATA KADAR HARGA KERJA BAGI TAHUN		*PURATA KADAR HARGA KERJA
			2008 (RM)	2009 (RM)	(RM)
22	Road surfacing; prime coat including all necessary works	M2	2.50	2.00	2.00
23	Road surfacing; tack coat including all necessary works	M2	4.27	4.90	5.00
24	Road furniture; pavement markings - continuous line; size 150mm wide	M	11.04	4.20	8.00
25	Road furniture; pavement markings - letters and shapes	NO	150.00	-	150.00
26	Road furniture; signages - illuminated complete with all necessary works	NO	250.00	250.00	250.00

* Purata Keseluruhan (rounded up) yang ditetapkan