

BAHAGIAN 3.14 : MISCELLANEOUS WORKS

Kawasan Utara - Perlis, Kedah, Pulau Pinang dan Perak
 Kawasan Tengah - Wilayah Persekutuan Kuala Lumpur, Melaka, Negeri Sembilan,
 Selangor dan Johor
 Kawasan Timur - Pahang, Terengganu dan Kelantan

BIL	KETERANGAN KERJA	UNIT	KAWASAN TENGAH		KAWASAN TENGAH		KAWASAN TIMUR		KESELURUHAN	
			PURATA (RM)	JULAT (RM)	PURATA (RM)	JULAT (RM)	PURATA (RM)	JULAT (RM)	PURATA (RM)	JULAT (RM)
1	Chain Link Fences; chain link, 1.80m high including all necessary mild steel post and concrete base, angle bracing and framing complete with painting	m			82.10	60.00 - 121.00			82.10	60.00 - 121.00
2	Fences; chain link, 2.10m high including all necessary mild steel post and concrete base, angle bracing and framing complete with painting	m	96.40	80.00 - 120.00					96.40	80.00 - 120.00
3	Fences; chain link, 2.25m high including all necessary mild steel post and concrete base, angle bracing and framing complete with painting	m			160.50	130.00 - 200.00			160.50	130.00 - 200.00
4	Chain Link Fencing with PVC Coated 2250mm height, complete with 3 nos of M.S. Gate along treatment plant area	m			114.65	90.00 - 150.00			114.65	90.00 - 150.00
5	Gates Mild steel double leaf sliding door gate overall size 3500mm width x 2100mm high consisting of 62.5mm x 62.5mm x 6.25mm thick painted steel angle posts including 2 nos of 100mm Diameter mild steel posts infilled with mass concrete, bolts and sleeve, lock plate, butt hinges, welding painting, excavation and any other necessary works and materials	no.	3,410.00	2,200.00 - 5,200.00					3,410.00	2,200.00 - 5,200.00

BAHAGIAN 3.14 : MISCELLANEOUS WORKS

Kawasan Utara - Perlis, Kedah, Pulau Pinang dan Perak
 Kawasan Tengah - Wilayah Persekutuan Kuala Lumpur, Melaka, Negeri Sembilan,
 Selangor dan Johor
 Kawasan Timur - Pahang, Terengganu dan Kelantan

BIL	KETERANGAN KERJA	UNIT	KAWASAN TENGAH		KAWASAN TENGAH		KAWASAN TIMUR		KESELURUHAN	
			PURATA (RM)	JULAT (RM)	PURATA (RM)	JULAT (RM)	PURATA (RM)	JULAT (RM)	PURATA (RM)	JULAT (RM)
6	Gates; Mild steel, overall size 6.0m x 1.80m high including all necessary mild steel poles and concrete post, angle framing and bracings, coated wire mesh, hinges, locks and other fixtures, finish and complete with painting	no.			3,131.90	2,000.00 - 5,200.00			3,131.90	2,000.00 - 5,200.00
7	Bearing Pads Supply and install in position fixed type laminated elastomeric bearing pad of size of 450 x 250 x 54mm thick inclusive of epoxy mortar bedding	no.					716.74	315.00 - 1250.00	716.74	315.00 - 1250.00
8	Supply and install in position free type laminated elastomeric bearing pad of size of 450 x 250 x 64mm thick inclusive of epoxy mortar bedding	no.					538.40	315.00 - 850.00	538.40	315.00 - 850.00
9	Allow for preliminary test to 450 x 250 x 54mm thick laminated elastomeric bearing pad at approved and accredited laboratory	no.					1,687.50	1,050.00 - 2,000.00	1,687.50	1,050.00 - 2,000.00
10	Allow for preliminary test to 450 x 250 x 64mm thick laminated elastomeric bearing pad at approved and accredited laboratory	no.					1,687.50	1,050.00 - 2,000.00	1,687.50	1,050.00 - 2,000.00