

BAHAGIAN 3.9 : BUILDING WORK

Kawasan Utara - Perlis, Kedah, Pulau Pinang dan Perak
 Kawasan Tengah - Wilayah Persekutuan Kuala Lumpur, Melaka, Negeri Sembilan, Selangor dan Johor
 Kawasan Timur - Pahang, Terengganu dan Kelantan

BIL	KETERANGAN KERJA	UNIT	KAWASAN UTARA		KAWASAN TENGAH		KAWASAN TIMUR		KESELURUHAN	
			PURATA (RM)	JULAT (RM)	PURATA (RM)	JULAT (RM)	PURATA (RM)	JULAT (RM)	PURATA (RM)	JULAT (RM)
	<u>Roofing Work</u>									
1	150mm x 75mm x 6mm thick 'C' Channel	m	92.75	55.00 - 150.00					92.75	55.00 - 150.00
2	76.2mm x 63.5mm x 7.90mm thick mild steel angle	no.	62.00	40.00 - 80.00					62.00	40.00 - 80.00
	<u>Water Proofing</u>									
3	SIKA PROOF 3000 AF, 3mm torch applied APP modified bituminous waterproofing sheet membrane reinforced with non woven polyester sand finish with warranty 10 years from the date of Practical Completion or any other approved equivalent. All the installation works to be manufacturer's details.	m2	37.64	30.00 - 55.00					37.64	30.00 - 55.00
	<u>Finishes</u>									
4	Wall Finishes 20mm thick (minimum) cement and sand (1:3) as described paving finished smooth with steel trowel	m2	16.60	15.00 - 25.00					16.60	15.00 - 25.00
5	Cement and sand (1:6) mixed with and approved plasticiser and finished with a wood float/trowel	m2	15.70	12.00 - 18.00					15.70	12.00 - 18.00