

**BAHAGIAN 3.8 : BRICKWORK, BLOCKWORK & MASONRY (CLASS J)**

Kawasan Utara - Perlis, Kedah, Pulau Pinang dan Perak  
 Kawasan Tengah - Wilayah Persekutuan Kuala Lumpur, Melaka, Negeri Sembilan,  
 Selangor dan Johor  
 Kawasan Timur - Pahang, Terengganu dan Kelantan

BIL	KETERANGAN KERJA	UNIT	KAWASAN UTARA		KAWASAN TENGAH		KAWASAN TIMUR		KESELURUHAN	
			PURATA (RM)	JULAT (RM)	PURATA (RM)	JULAT (RM)	PURATA (RM)	JULAT (RM)	PURATA (RM)	JULAT (RM)
1	<b>BRICKWORK</b> 115mm Thick common clay brickwall laid on cement and sand mortar (1:3) mortar with an approved plasticiser as described including layer of exmet at every fourth courses as described	m2			45.95	32.60 - 52.00			45.95	32.60 - 52.00
2	Construct 230mm thick cement sand brickworks in cement mortar (1:3), all exposed surfaces of walls rendered with 20mm thk.cement and sand (1:3)	m2			76.50	40.00 - 100.00			76.50	40.00 - 100.00
3	Construct 345mm thick cement sand brickworks in cement mortar (1:3), all exposed surfaces of walls rendered with 20mm thk.cement and sand (1:3) as described	m2			102.50	70.00 - 150.00			102.50	70.00 - 150.00
4	<b>DECORATIVE WALL PANEL</b> Supply and install decorative pre historic wall panel as per detailed drawing and instruction	m2			165.00	65.00 - 560.00			165.00	65.00 - 560.00