

BAHAGIAN 3.16 : MISCELLANEOUS WORKS (CLASS T)

BIL	KETERANGAN KERJA	UNIT	PURATA KADAR HARGA 2013 (RM)			
			KAWASAN UTARA	KAWASAN TENGAH	KAWASAN TIMUR	KESELURUHAN
FENCES						
1	Fences; chain link; supply and fix 2.8m high uPVC coated mesh complete with galvanised conner, intermediate, staining post and 450mm high barbed wire. Rate to include concrete stump, kerbs and all necessary excavation.	m		152.36		152.36
2	Fences; chain link; supply and fix 1.8m high uPVC coated mesh complete with galvanised conner, intermediate, staining post and 450mm high barbed wire. Rate to include concrete stump, kerbs and all necessary excavation.	m		115.10		115.10
GATES						
3	Supply, erect and paint 5.053m wide x 3.0m high double leaf galvanised and uPVC coated gate complete with hinges, lock and 450mm high barbed wires.	no.		2,912.00		2,912.00
4	Single leaf SSM steel gate 900 mm x 2400 mm high, consisting of 38 x 38 x 2.3 mm thick rectangular hollow section as frame welded together with 75 x 75 x 2.3 mm thick square hollow section; including painting, ironmongery; fixing with hinges on lugs built in masonry backing.	no.		1,495.25		1,495.25
5	Double leave mild steel gate 4000 mm x 2400 mm high, consisting of 38 x 38 x 2.3 mm thick square hollow section; including painting, ironmongery; fixing with hinges on lugs built in masonry backing.	no.		3,561.40		3,561.40

BAHAGIAN 3.16 : MISCELLANEOUS WORKS (CLASS T)

BIL	KETERANGAN KERJA	UNIT	PURATA KADAR HARGA 2013 (RM)			
			KAWASAN UTARA	KAWASAN TENGAH	KAWASAN TIMUR	KESELURUHAN
BEARING PADS						
6	475mm x 475mm x 45mm thick Laminated Elastomeric bearings (fixed) on minimum 25mm thick epoxy resin mortar Grade 70.	no.		623.00		623.00
7	475mm x 475mm x 60mm thick Laminated Elastomeric bearings (free) on minimum 25mm thick epoxy resin mortar Grade 70.	no.		750.00		750.00