

**BAHAGIAN 3.3 : DEMOLITION & SITE CLEARANCE (CLASS E)**

BIL	KETERANGAN KERJA	UNIT	PURATA KADAR HARGA 2013 (RM)			
			KAWASAN UTARA	KAWASAN TENGAH	KAWASAN TIMUR	KESELURUHAN
<b>GENERAL CLEARANCE</b>						
1	General site clearance of reserve indicated in the drawing or as directed by the S.O. including filling and disposal of trees, bushes, demobilisation of crossing, structures and other obstruction along the channel alignment and dispose off site to contractor own tips.	Ha		2,150.00		2,150.00
2	Site clearing the reserve width of the river.	Ha		2,000.00		2,000.00
3	Clear and remove all bushes, undergrowth, shrubs, rubbish, and debris including grubbing up roots, dispose as specified and directed by S.O.	Ha	2,730.00	2,650.00		2,690.00
4	Clear the whole site of small trees, shrubs bushes and grubbing up roots and refilling with approved selected earth, clearing all under-growth and other vegetation, debris, rubbish and dispose from site to Contractor's own dump.	m2		1.11		1.11
<b>TREES</b>						
	<u>Cutting down and dispose of trees having a girth of</u>					
5	1-2m	no.		92.50		92.50
6	2-3m	no.		140.00		140.00

**BAHAGIAN 3.3 : DEMOLITION & SITE CLEARANCE (CLASS E)**

BIL	KETERANGAN KERJA	UNIT	PURATA KADAR HARGA 2013 (RM)			
			KAWASAN UTARA	KAWASAN TENGAH	KAWASAN TIMUR	KESELURUHAN
<b>BUILDINGS / STRUCTURES / PIPELINES</b>						
	<u>Demolition and removal from worksite and dispose off site to contractor's own dumping ground of existing structures and obstructions.</u>					
7	House or building					
	i) Not higher than two storey	no.		2,560.00		2,560.00
	ii) Higher than two-storey	no.		3,720.00		3,720.00
8	Pipe culvert	no.		1,380.00		1,380.00
9	Manhole or sump	no.		95.00		95.00
10	Existing Road	m2		4.50		4.50
11	Existing Concrete Drain	m		12.00		12.00
12	Existing Concrete Slab (with / without reinforcement)	m3		102.00		102.00