

**BAHAGIAN 3.8 : BRICKWORK, BLOCKWORK & MASONRY (CLASS J)**

BIL	KETERANGAN KERJA	UNIT	PURATA KADAR HARGA 2013 (RM)			
			KAWASAN UTARA	KAWASAN TENGAH	KAWASAN TIMUR	KESELURUHAN
<b>BRICKWORK</b>						
1	115mm Thick common clay brickwall laid on cement and sand mortar (1:3) mortar with an approved plasticiser as described including layer of exmet at every fourth courses.	m2	38.40	40.20	42.00	40.20
2	Construct 230mm thick cement sand brickworks in cement mortar (1:3), all exposed surfaces of walls rendered with 20mm thk.cement and sand (1:3).	m2			88.00	88.00
3	6 mm diameter mild steel bonding ties 300 mm girth with one hooked into joint of brickwork including forming perforation of formwork.	no.		2.45		2.45
4	Damp proof course as described to 225mm wide.	m		3.57		
5	Damp proof course as described to 115mm wide.	m		2.96		